

### **Dublin City Council Briefing**

May 20, 2024



### Overview



- Why we need a new water plant and transmission mains
- How do these projects fit into the system
- Goals for the transmission mains
- Evaluation process
- Corridor recommendations
- Schedule
- Next steps





### Why We're Building a Water Plant



The continued growth of population and industry in central Ohio, along with the need to increase reliability and resiliency across the water supply system, has driven the need for additional water capacity.


- 1998-Water Beyond 2000 Report
- Water Master Plans updated every 10 years
- Three existing water plants supply an average of 145 MGD





### How do these projects fit into the system





### Goals for the Transmission Mains




- Select the most technically feasible, reliable, resilient, constructible routes
- Collaborate with stakeholders on potential capital investments
- Be transparent with the public; demonstrate how we selected the recommended corridors
- Communicate what we are doing
- Minimize disruptions to the extent possible





### Project Scope

- Water plant (partial) & one main scheduled to be online by 12.31.2028
- Evaluate 14 corridors
- Two mains (for resiliency and reliability) from the water plant to the connection point at Frantz and Parkcenter
- One river crossing



### **Evaluation Process**




- Aerial mapping
- OUPS calls
- Preliminary base mapping
- Prepared evaluation guidelines
- Alignment layout to compare corridors (over 100 miles was evaluated)
- Site visits
- Pairwise comparison
- Risk analysis
- Cost estimates





### **Evaluated Over 100 Miles**





**Dublin Council Briefing** 

All alignments reviewed total over 100 miles

# Evaluation Process: Drawings


















90034202025000

LUAMS KURT E MARLYN MAD SON 123 SOUTT FARKVILW DIE





# Evaluation Process: Pairwise Comparison



PRIORITY SCALE									
EXTREMELY MORE IMPORTANT	MODERATELY MORE IMPORTANT	EQUALLY IMPORTANT	MODERATELY LESS IMPORTANT	EXTREMELY LESS IMPORTANT					
5	3	1	1/3	1/5					

Critorio Dankina

	Ci	riteria Rankii	ng	
EASEMENTS	TRAFFICIMPACT	ENVIRONMENTAL IMPACT	BUSINESS IMPACT	ACCESSIBILITY
1	3	1	3	1
1/3	1	1/3	1/3	1/5
1	3	1	3	1
1/3	3	1/3	1	1/3
1	5	1	3	1

Ge om etric Mean	Normalized Weigl
.552	0.266
.375	0.064
.552	0.266
.644	0.110
.719	0.294
.842	1.000





ACCESSIBILITY

**BUSINESS IMPACT** 

ENVIRONMENTAL IMPACT

EASEMENTS
TRAFFIC IMPACT

# Evaluation Process: Risk Analysis



	Risk score m	<u>natrix</u>				
	5	5	10	15	20	25
nce	4	4	8	12	16	20
Consequence	3	3	6	9	12	15
Cons	2	2	4	6	8	10
	1	1	2	3	4	5
	Rating	1	2	3	4	5
				Likelihood		
		NEGLIGIBLE	MINOR	MODERATE	MAJOR	CATASTROPHIC
Cost		\$< 250k	250k<\$< 1M	1M<\$<2M	2M<\$<5M	\$>5M
Time		T<1w	1w <t<4w< td=""><td>1m<t<3m< td=""><td>3m<t<6m< td=""><td>T&gt;6m</td></t<6m<></td></t<3m<></td></t<4w<>	1m <t<3m< td=""><td>3m<t<6m< td=""><td>T&gt;6m</td></t<6m<></td></t<3m<>	3m <t<6m< td=""><td>T&gt;6m</td></t<6m<>	T>6m





### **Evaluation Process: Risk Analysis**



						ه مر	Initial Severity			
Date Added	RiskID	Phase/Location	Risk Description	Cause(s)	Effect(s)	Likelihood o	Cost	Time	Other	Score
4/5/2023	2.00.01	ROW	Insufficient lay-down area at site locations	inadequate work areas acquired for project	increased costs and schedule delays	5	3	5		25

	Mitigation Measures		Current/Residual						
			Severity		ty				
			Cost	Time	Other	Score	Action Items	Action Item Completion Date	Res pons ible Party
		5	3	5	0	25	<ol> <li>Review work areas for planned activities at each site during preliminary design.</li> <li>Confirm work areas for planned activities at each site during detailed design.</li> </ol>	6/14/2024 12/20/2025	Ken Ricker





### **Evaluation Process: Cost Estimates**



	WATER TRANSMISSION MAINS							
	ITEM DESCRIPTION	QUANTITY	UNIT	UNIT COST*	TOTAL	BID PCKG	CODE	COMMENTS
G	Alignment - G			\$2,901.59	\$168,437,417			58,050 LF route
	Distance of Venter	50.050	LF	#700 pp	*40.404.645			
	Piping and Vavles	58,050		\$730.83	\$42,424,615		_	
G1	54" PCCP Pipe, material and labor	31,977	LF	\$730.00	\$23,343,210		G	Sheets 15-50, Transition 177+25
G2	54" PCCP Pipe, material only for trenchless installation	8,348	LF	\$635.00	\$5,300,980		G	Sheets 15-50, Transition 177+25
G3	42" PCCP Pipe, material and labor	14,595	LF	\$495.00	\$7,224,525		G	Sheets 1-15, Transition 177+25
G4	42" PCCP Pipe, material only for trenchless installation	3,130	LF	\$430.00	\$1,345,900		G	Sheets 1-15, Transition 177+25
G5	54" BFV Valve, Manual, Flanged, in Precast Valve Vault	40	EA	\$110,000.00	\$4,400,000		G	Assume every 1,000 LF
G6	42" BFV Valve, Manual, Mechanical Joints, Direct Buried	18	EA	\$45,000.00	\$810,000		G	Assume every 1,000 LF
l	Trench Under Pavements	31,672	LF	\$725.61	\$22,981,445			Below all Pavements: 31,672 LF
G7	Excavate Trench: 9' wide, 15' Deep, using Trench Box	158,360	CY	\$12.00	\$1,900,320		G	Exclude portions at Trenchless
G8	Haul Spoils Off Site, 30 miles each way	158,360	CY	\$24.00	\$3,800,640		G	
G9	Bedding #57 Stone: 9' wide, 6" high	5,279	CY	\$70.00	\$369,507		G	
G10	Haunching #57 Stone: 9' wide, 2'-9" high	17,486	CY	\$70.00	\$1,223,991		G	
G11	Above Haunching #304 Granular: 9' wide, 3'-9" high	28,043	CY	\$60.00	\$1,682,575		G	
G12	Final Backfill #304 Granular: 9' wide, 8' high	84,459	CY	\$60.00	\$5,067,520		G	
G13	9" Asphalt over 4" of #304 Granular Base, incl. Berm an 4" Pipe	732,768	SF	\$12.01	\$8,800,544		G	Roadway: 30,532 LF x 24' wide
	Uderdrain per County Standards, incl. Pavement Demo							
G14	6" Asphalt on 6" of #304 Granular Base at Drives, incl. Demo	14,160	SF	\$8.85	\$125,316		G	Drives: 1,180 LF x 12' wide
G15	4" Asphalt on 4" #304 Granular Base at Bike Paths, incl. Demo		SF	\$6.50			G	Bike Path: 0 LF x 8' wide
G16	4" Concrete on 4" #304 Granular Base at Walks, incl. Demo	1,100	SF	\$10.03	\$11,033		G	Sidewalks: 220 LF x 5' wide
	Trench Outside Pavements	14,900	LF	\$295.39	\$4,401,357			Outside Pavements: 14,900 LF






### Alignment A

#### Not selected. Main reasons:


- Narrow corridor & numerous utilities in Historic Dublin
- Environmental concerns
  - Potential threatened species
- Archeological & Cultural concerns
  - Cemeteries, Stone wall
- Significant road closures
- 87 Easements
- Highest ranked risk alignment
- Highest ranked pairwise alignment
- Note: Cheapest alignment by \$50M.



# Alignment B

#### Main reasons not selected:


- Environmental concerns
  - Potential threatened species
- Significant road closures
- River crossing concerns
  - high risk trenchless installation with deep access shafts to cross river downstream of O'Shaughnessy Dam
- Second highest ranked risk alignment
- Cost (\$40M more than recommended. alignment)



# Alignment C

#### Main reason not selected:


• EPA pressure requirements



# Alignment D

#### Main reason not selected:


- EPA pressure requirements
- SR 33/Avery/Muirfield Interchange



# Alignment E


#### Main reasons not selected:

- EPA pressure requirements
- SR 33/Avery/Muirfield Interchange



# Alignment F


Portion of Alignment F is recommended



### Alignment G

#### Recommended

- Least amount of easements
- Best ranked risk alignment
- Best ranked pairwise alignment
- Cost




# **Alignment Summary**

		North/South Alignments									
	Α	В	С	D	E	F	G				
Total Length (LF)	44,200	58,700	71,989	66,955	60,600	60,663	58,050				
Total Easements	87	19	85	92	50	37	18				
Cost	\$250M	\$342M	\$335M	\$351M	\$296M	\$302M	\$303M				
						-					
Cost Rank	1	6	5	7	2	3	4				
Pairwise Rank	7	3	2	4	5	6	1				
Risk Rank	7	6	2	4	5	3	1				

#### Notes:

- 1. Cost includes assumptions for rock excavation, dewatering, utility conflicts, traffic control, and tree removal/restoration.
- 2. Cost includes assumptions for general conditions, bonds, insurances, mobilization, phasing premium, escalation, construction contingency, and owners contingency.



### River Crossing Alignments


#### I-270 vs Henderson Road

Hydraulic model showed I-270 best location

#### I-270S vs I-270N


- I-270S less easements
- I-270S less risk
- I-270N Environmental concerns

I-270S River Crossing Recommended




# East/West Alignments


Emerald E/W Connector is Recommended



### Corridor Recommendations

- Pipe size: two N/S 48-inch mains
- Cost for N/S mains=\$438M





### Schedule





January 2023 – August 2024 PHASE 2 FINAL DESIGN

March 2024 – June 2026

PHASE 3
CONSTRUCTION

2027 - 2030





### Public Outreach




- Website https://cbuswater4.com/
- Letters
- Door hangers
- Dublin weekly soil boring updates
- **Business cards**













### Public Meeting on June 18



- In-Person Public Meeting
  - Tuesday, June 18, 2024 6:00-8:00 PM
  - Dublin Community Recreation Center (Talla Rooms)
  - 5600 Post Rd, Dublin, OH 43017
- Virtual Recording
  - https://cbuswater4.com/
  - Available online after the June
     18 in-person public meeting







### Next Steps



- Survey, geotech borings, utility locate, field walks
- Public meeting on June 18
- Move to final design phase
  - Memorial Tournament, Irish Festival, Independence Day
  - Preserve mature trees & landscaping
  - Keep public informed
- Jurisdictional design review and/or other meetings
- Coordinate construction with local Capital Improvement Programs





# Thank You



